

# INTEGRASPEC<sup>®</sup>

"The User Friendly ICF"

## FEATURE PROJECT



**Project:** Family Vision Center

**Creston, Iowa**

**Architect / Engineer:** Laugerman and Associates

**West Des Moines, Iowa**

**General Contractor:** Cornerstone Commercial

**Corning, Iowa**

**ICF Installer:** TEK Builders Inc.

**Mt. Ayr, Iowa**

**ICF Distributor:** IntegraSpec Midwest

**Mt. Ayr, Iowa**

**Features:** This 4,200 ft<sup>2</sup> professional building features masonry and Hardie Board, complete with 6" reinforced concrete core IntegraSpec<sup>®</sup> wallsystem.

**Benefits:** IntegraSpec<sup>®</sup> wallsystem provided a fast and accurate construction. 6" IntegraSpec<sup>®</sup> walls 12' high were poured to the top in one lift eliminating potential cold joints and saving pump time and labour costs.

*"As always, this wall was poured with no problems or form failures. We pumped 55 cubic yards in 280 linear feet of 12' wall in one hour and forty five minutes. That saved pump time versus the time it took when we built with other ICFs, and the form waste filled only one large garbage bag. Incredible!!"*

*- Kelly Main  
Certified Installer*

**Specify *Integrity* in your next project:**

Please visit us at [www.integraspec.com](http://www.integraspec.com)

